

# JAMMU MUNICIPAL CORPORATION

## Trikuta Division

### Short Tender Notice Inviting e-Tender

For and on behalf of The Commissioner, Municipal Corporation, Jammu. The Executive Engineer, Trikuta Division, Municipal Corporation, Jammu invites online tenders from registered class of contractors / Firms as per the prescribed format for the following works.

The online / e-tenders along with the scanned CDR and other documents should be uploaded on or before 11.02.2017 up to 1400 Hrs. The original instruments should be submitted in the office of Executive Engineer, Trikuta Division, Jammu Municipal Corporation, Jammu, well before the bidding date. The CDR is to be pledged to the Executive Engineer-T, Jammu Municipal Corporation.


Other details and terms /Conditions are contained in the NIT and can be seen and downloaded from the Site [www.jktenders.gov.in](http://jktenders.gov.in).

| S.NIT No. | Particulars   | Apx. Cost (In Lacs) | Earnest Money (in Rupees) | Cost of Tender Document (in Rupees) | Class Of Cont. | Time Of Comp. |
|-----------|---|---------------------|---------------------------|-------------------------------------|----------------|---------------|
| 486 t     | Construction of Community Hall near Durga Temple at Mohalla Vikram Chowk near Amar Singh Club, Jammu ward No: 19. | 3.70                | 3700                      | 600/-                               | SHG            | 40 Days       |

#### TERMS & CONDITIONS:

1. Tenders without CDR are liable for cancellation.
2. Prior to bidding sales tax clearance certificate of the proceeding year issued by sales Tax Deptt. must be uploaded and enclosed with the hard copy.
3. The bids shall be uploaded in electronic format on the website <http://jktenders.gov.in>.
4. The original instrument in respect of CDR & others must be delivered to Executive Engineer, Trikuta Division through by Registered post/Speed post / courier or by hand, On or before due date.
5. The Department Reserves the right to disqualify any bidder who even uploads the bid documents but without submitting the original instrument in the office in time.
6. Registration card should have been renewed for the year 2016-17 well before the Date & receipt of tender, if not the same shall be entertained only after production of proof of remittance of renewal fee in the concerned office (Ref. to GR).
7. In case the amount / rate quoted by the tenderer / bidder is less than 15% of the advertised amount the bidder shall upload and enclosed an additional security deposit in shape of CDR @ 5% of the advertised amount at the time of initial bidding. Bids which fall in the above category & are not accompanied by the necessary additional security deposit shall be straightaway rejected.
8. Photocopies of pan card, registration card and sales tax should be self attested or attested by the Gazetted officer.
9. If the quoted rates are 40% below then the rates advertised it will be considered as non responsive bid and will not be considered.

No: MJ/Tech/T/ 9853-60  
Dt: 24-01-17  
Copy to the:

  
Executive Engineer-(T)  
Jammu Municipal Corporation.

1. Commissioner, Jammu Municipal Corporation for information
2. Joint Commissioner (W), Jammu Municipal Corporation for information
3. Chief Accounts Officer, Jammu Municipal Corporation for information
4. AEE (Concerned), Jammu Municipal Corporation for information.
5. A.A.O for information.
6. H.D for information
7. I/C e.tendering JMC for information and necessary action.

**RTISE RATE LIST FOR Construction of Community Hall near Durga Temple at Mohalla Vikram Chowk  
Amar Singh Club, Jammu Ward No. 19.**

RTISED COST: Rs. 3.70 Lacs.

Time of Completion: 40 Days

|  | Description  | Unit     | Qty.   | Rate           |
|--|--|----------|--------|----------------|
|  | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 m lead. 1:3:6 or richer mix.  | Cum      | 4.21   | 813.85         |
|  | Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not Exceeding 1.5 m in width) and for shafts, wells, cesspits and the not exceeding 10 Sqm on plan, depth up to 1.5 mtr. incl. disposal of excavated earth up to 1 mtr for cutting edge. disposed earth is to be leveled and neatly dressed in all kinds of soils. | Cum      | 13.06  | 240.45         |
|  | Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead.<br>In cement mortar  | Cum      | 11.29  | 687.55         |
|  | Providing & laying in position cement concrete of specified grade excluding the cost of centring & shuttering -All work up to plinth level. 1:5:10 Cement: 5 Coarse sand: 10graded stone agg. 40mm nominal size). Crushed  | Cum      | 3.46   | 2750.40        |
|  | Providing & laying in position cement concrete of specified grade excluding the cost of centring & shuttering -All work up to plinth level. 1:3:6(1 Cement: 3 Coarse sand: 6graded stone agg. 20mm nominal size) Crushed.  | Cum      | 14.53  | 3707.40        |
|  | Dumping / filling of stones including cost of stones. In horizontal on level.  | Cum      | 3.63   | 327.05         |
|  | Brick work with common burnt clay F.P.S (non - modular) bricks of class designation 75 in Foundations & plinth in cement mortar 1:6 (1 cement: 6 coarse sand).<br>Extra for brick work in super structure above plinth level up to floor V level(by manual means)  | Cum      | 17.31  | 5257.95        |
|  | Providing & laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement-All work up to plinth level. 1:1.5:3(1 Cement: 1.5 Coarse sand: 3graded stone agg. 20mm nominal size).  | Cum      | 3.99   | 5504.20        |
|  | Centring and shuttering including strutting propping etc. and removal of form work for; Foundations, footings, bases of columns etc. for mass conc..   | Sqm      | 53.02  | 179.25         |
|  | Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars..  | Kg.      | 355.00 | 71.00          |
|  | Centring and shuttering including strutting, propping etc and removal of the form work for:<br>Suspended floors, roofs, landing, balconies and access platform.  | Sqm.     | 31.94  | 372.40         |
|  | Centering & shuttering (form work) incl. strutting propping etc. & removal of form work for Edges of slabs and Breaks in floors and walls under 20cms wide..   | Mtr      | 23.78  | 176.55         |
|  | 15mm Cement plaster on the rough side of single or half brick wall of mix.<br>1:6(1 cement :6 Coarse sand)   | Sqm      | 151.48 | 164.40         |
|  | Kota stone flooring over 20mm (av.) thick base laid over & jointed with grey cement slurry mixed with pigment to mach the shade of the slab incl.rubbing & polishing complete with base of 1:4 (1 cement :4 coarse sand) 25mm thick.   | Sqm      | 23.42  | 1530.15        |
|  | Providing and fixing of Angle iron Chowghats (Complete Job)  | No.      | 2.00   | 3500.00<br>LMR |
|  | Providing and fixing of Angle iron Windows (Complete Job)  | No.      | 2.00   | 5000.00<br>LMR |
|  | Providing and fixing of Electric points including all necessary fittings (complete Job)  | Points   | 10.00  | 1000.00<br>LMR |
|  | Providing & fixing 1.0 HP Electric Motor Complete Job. (as per the directions of Engineer Incharge.)<br>Crompton graves / sharp / Usha   | No.      | 3.00   | 5500.00<br>LMR |
|  | Providing & fixing G.I pipe complete with G.I fittings & clamps including cutting & making good the walls extra inertial work (Exposed on walls) internal 20 mm dia nominal bore (medium)  | Mtr      | 169.75 | 227.85         |
|  | Carriage of materials by mechanical transport including loading / unloading & stacking complete  |          |        |                |
|  | > Sand for an average distance of 4 kms  | Cum      | 14.15  | 117.14         |
|  | > Stone aggregate below 40mm Nominal size Crushed for an average distance of 7 kms   | Cum      | 19.31  | 144.96         |
|  | > Stone for an average distance of 4 kms   | cum      | 3.63   | 137.81         |
|  | > Bricks for an average distance of 15 kms   | 1000 No. | 8222   | 554.24         |

1. The quantities shall be executed as per necessity at site only.
2. Any item or items beyond the above advertised rate list / quantity schedule if found necessary during the execution of the said work the same shall be paid as per SSR of 2012 subject to the contractors appreciation / Depreciation for the items beyond the advertised rate list.
3. Any typographical error if found in the above rate list / quantity schedule the same shall be corrected accordingly & shall be paid as per SSR of 2012 with the contractors appreciation / Depreciation.

A.E.E

  
**Executive Engineer,**  
 Municipal Corporation Division (T),  
 Trikuta Complex Dogra Hall Jammu